

Mark J. Sobeck Roof Consulting, Inc.
Roof Consultant
161 Main Street, Suite 300
Luzerne, PA 18709
(570) - 829 - 5777

Revision Schedule			24014
NO.	DESCRIPTION	DATE	
			BUILDING E ROOF REPLACEMENT

UPMC LIFE CHANGING MEDICINE

DATE

rmcreative
Architects and Interior Designers

RM Creative Inc
20 Starview Street, Suite 701
Pittsburgh, PA 15222
o 412.471.4445
w RMCreative.com

Mark J. Sobczek Roof Consulting, Inc.
Roof Consultant
161 Main Street, Suite 300
Lucerne, PA 18759
(570) - 829 - 5777

NOTES

N

PROJECT

UPMC ALTOONA
BUILDING E ROOF REPLACEMENT

DRAWING NAME

**COVER SHEET
AND CODE SUMMARY**

OWNER/PROJECT NUMBER

240093

PROJECT NUMBER

24014

DATE

12/17/24

ISSUED FOR

CONSTRUCTION

G001

INDEX OF DRAWINGS

G001	COVER SHEET	AND CODE SUMMARY
ARCHITECTURAL		
AD101	DEMOLITION PLAN	
A101	ROOF CONSTRUCTION PLAN	
A102	ROOF DETAILS	
A103	7TH FLOOR PLAN	(FOR REFERENCE)

GENERAL PROJECT NOTES

1. Do not scale drawings.
2. Dimensions are to column centerline, face of finish, face of masonry, or face of foundation wall, unless noted otherwise.
3. Verify dimensions of existing conditions at the site. Report discrepancies to Architect before proceeding with work.
4. Freeze penetrations through rated systems.
5. Retain and protect items designated for reuse within the project. Return items to Owner as indicated.
6. Limits of project are shown for general reference only and do not establish precise boundaries of work for any trade that may be required to complete the project.
7. Review status of salvagable material with Owner prior to removal from the site.

CODE SUMMARY

LIFE SAFETY CODE	NFPA 101: 2012
BUILDING CODE	IBC: 2018
MECHANICAL CODE	IBC: 2018
PLUMBING CODE	IPC: 2018
ELECTRICAL CODE	IBC: 2018
FIRE PROTECTION CODE	IBC: 2018
ENERGY CODE	IEBC: 2018
ACCESSIBILITY	ANSI 117.1 / CHAP 11, IBC 2018

CODE SUMMARY		IBC 2018	NFPA 101 2012
OCCUPANCY	12 INSTITUTIONAL (HOSPITAL)	NEW HEALTH CARE	
TYPE OF CONSTRUCTION	TYPE I@	TYPE A (222)	
SPRINKLERED	FULLY SPRINKLERED	FULLY SPRINKLERED	
FIRE RESISTANCE RATING	TABLE 601	TABLE A.8.1.2	
COLUMNS	2 HOURS	2 HOURS	
BEAMS	2 HOURS	2 HOURS	
FLOOR CONSTRUCTION	2 HOURS	2 HOURS	
ROOF CONSTRUCTION	1 HOUR	1 HOUR	
THIS BUILDING IS EQUIPPED WITH AN AUTOMATIC SPRINKLER SYSTEM			

THIS BUILDING IS EQUIPPED WITH AN AUTOMATIC SPRINKLER SYSTEM

DRAWING SYMBOLS

	ROOM NAME, NUMBER, AREA		EXISTING CONSTRUCTION TO REMAIN
	SECTION TAG		REMOVE EXISTING CONSTRUCTION
	INTERIOR ELEVATION TAG		NEW CONSTRUCTION
	EXTERIOR ELEVATION TAG		EXISTING DOOR
	DETAIL CALLOUT TAG		NEW DOOR
	CEILING HEIGHT TAG		DOWNLIGHT
	COLUMN TAG		LIGHT FIXTURE
	QUOIN		DIFFUSER
	KEYED NOTE		RETURN
	FINISH/CASEWORK TAG		
	EQUIPMENT TAG		WINDOW TAG
	PARTITION TAG		ACCESSORY TAG


ABBREVIATIONS

[illegible]


ABBREVIATIONS

HT	Height
HPR	High Impact Resistant
IM	Imitation
HDRZ	Horizontal
IC	Interlocking
IS	Inside Direction
INS	Insulation
LT	Location
MFR	Memory
ME	Memory
MECH	Mechanical
MO	Moisture
MR	Moisture Resistant
MS	Moisture Sensitive
NTS	Not to Scale
OC	On Center
OPG	On Opposite Hand
OS	Opening
PE	Outside Direction
PEDIM	Partial
P-LAM	Plastic Laminate
P	Power
PLRG	Plumbing
PM	Painting Contractor
PT	Paint
P	Power
PLG	Plumbing
RWC	Rainwater Collector
REIN	Reinforcing / Reinforcing
RESL	Resilient
R	Roof
RD	Roof Drain
RO	Roof Opening
RT	Roof Trim
SPEC	Specification
STN	Stainless Steel
STRUCT	Structural
STL	Steel
TBL/AM	Top of Beam
T/MS	Top of Masonry
TYP	Typical
UNO. D.	Unfinished Otherwise
V.F.F.	Vertical Finish
V	Vert
W	Wood
WP	Work Point

LOCATION MAP



AREA MAP




ADDRESS:
620 Howard Ave, Altoona, PA 16601

© 2021 IBM Corporation

[illegible]

- UPMC **LIFE
CHANGING
MEDICINE**
- 2014
- 
- rmcreative**
Architects and Interior Designers
- RM Creative Inc.
20 Starview Street, Suite 701
Pittsburgh, PA 15202
o 412.471.4445
i @rmcreative.com

310.0 SQ FT	
65.0 SQ FT	
17.2 SQ FT	
14.4 SQ FT	
11724.6 SQ FT	
<i>N</i> ... 15.0 EA	
3795.5 SQ FT	
526.9 FT	



Note: Alternate No. 1 - Provide galvanized metal platform with railings and stairs with railings (detailed design) in lieu existing/new wood system (keyed note 1). Provide galvanized metal stairs with railings (detailed design) in lieu new wood system (keyed note 2).

- 1 Reinstall salvaged wood platform and railings. Modify platform support legs to align with floor slab based on new roof system thickness. Provide new treated wood stairs and railings based on new height. Provide 1" deep troughs and provide risers to be uniform in height. Provide concrete pavers under each platform support and at the bottom of the stairs.
- 2 Provide new treated wood stairs and railings based on new height. Provide 1" deep troughs and provide risers to be uniform in height. Provide concrete pavers under stair support and at the bottom of the stairs.
- 3 Reinstall salvaged concrete pavers - See Scope of Work Document for additional information.
- 4 Furnish and install new concrete pavers - See Scope of Work Document for additional information.

24014

CONSTRUCTION